SIGNAL COST ESTIMATE

ESTIMATE No:

UMA-TOR E073-033-01

Mile:

45.47

Location:

Castlemore Avenue

Dated: Subdivision:

Province:

Project Number:

Februrary 25 '05

Uxbridge Ontario

Project Description:

UMA WO Number:

ESTIMATED	COST FOR	RAILWAY	PART	OF WORK

RAILWAY MATERIAL

Insulated Joints.

\$9,476

RAILWAY LABOUR

Labour Signals

\$781

Labour Install Insulated Joints.

\$402

LABOUR OVERHEADS Labour Flagging (Flat Rate)

117.0% \$1,384

\$6,800

RAILWAY OTHER

Living Allowance

\$ 434

Equipment

\$2,750

Contract Overheads

\$3,204

TOTAL ESTIMATED RAILWAY COST

\$25,231

TENDERED CONTRACT TO INCLUDE ALL MATERIAL AND LABOUR WITH FOLLOWING

GUIDELINES

Description

Gate Mechanisms c/w barrier arms & lights.

Bells c/w mounting mechanism.

Battery cells & chargers/rectifiers

Grade Crossing Predictor

Housings

Foundations & Cribbing

Track connections

Wire & Cable

Highway Crossing Data Recorder

Fill for Gates & Housing

Complete Circuit Design & Plans (Hard Copy & CD)

Complete Installation

Test and place in service

CONTRACT COST FOR INSTALLATION OF AWD'S

CONTRACT CONTINGENCIES

10.0%

\$162,184

UTILITIES (Hydro Service)

\$16,218 \$5,000

TOTAL ESTIMATED SIGNAL CONTRACTOR COST

\$183,402

CONSULTING FEES

\$0

TOTAL ESTIMATED COST FOR PROJECT

\$208,633

NOTES: RE THE ESTIMATE

All applicable taxes, except GST, and service costs for locates and permits are included in the tender.

All Equipment to meet or better AREMA Standards. All construction work to be done to AREMA or CN/CP Rail Standards, whichever is the most restrictive. All Engineering work, including design and "in service testing", is to be done within the guidelines of the Railway Safety Act Section 11.

Parties Subject to G.S.T. will have 7% GST Applied to Their Costs

Canadian Transportation Agency Overhead Rates Used for the Railway portion of the Estimate

Billing Will Be At Actual Costs Plus Overheads

Estimate Does Not Include Railway Flagging Required for Road Construction.

Estimate Does Not Include Relocation of Utilities

Estimate is based on work during frost free ground conditions

Estimate is subject to revision.

Estimate Revision 0